

H7 – Norpipe – Discharge for the NGT Emden



Project Description: Shutdown of a North Sea compressor platform

Scope of Work: Using a bypass, the existing pig trap for taking in 11 pigs and approx. 600 m³ of seawater//glycol was extended about 20 metres and equipped with a temporary discharge. The pig trap door was cut off and replaced with a rapid closure door through an extension.

Special Features: Because of the 67 mm wall thickness, extensive preparation work (machine cutting, manufacture of chamfers, heat treatment, etc.) was necessary before carrying out the welding work.

Contractor: PPS, Business Unit WINTER ROHRBAU
Telephone : +49 (0) 5431 14 -0, Fax : +49 (0) 5431 14 - 260

Customer: Gassco AS, Subsidiary Emden, Germany