

Partial Renovation of Natural Gas Line 35



Project Description:

Partial renovation of natural gas line 35
- 44 renovation measures DN 500 / 600

Scope of works:

- 14 x jacket pipe renovation
- 11 x removing of jacket pipe with exchange media pipe
- 2 x valve group refurbishment
- 7 x valve group removal
- 1 x lifting a valve group
- 3 x siphon replacement
- 5 x extension of above ground pipelines (pipe bridge)
- 1 x repairing areas of insufficient coverage

PPS Pipeline Systems GmbH Work

- 2 x renovate 2 gate valve groups
- 1 x extension of above ground pipeline (pipe bridge)
- 4 x jacket pipe renovation
- 3 x extension of valve group / install adapter
- 5 x extension of jacket pipe

Contractor: PPS, WINTER ROHRBAU, Leipzig Office
Phone +49 (0) 34205 426 - 0, Fax +49 (0) 34205 426- 426
Execution as Joint Venture
Assigned measures completed independently by each Joint
Venture partner

Customer: VNG Verbundnetz Gas AG

Project Time Period: June – September 2006